

LAKE FRONT PARK EPA GREEN INFRASTRUCTURE					Telamon Construction Company				K F Construction & Excavating Inc				Barnes Nursery Inc				Smith Paving & Excavating				F. Buddie Contracting Inc							
REF. NO.	ODOT ITEM	ITEM DESCRIPTION	QNTY USED	UNIT	LABOR UNIT PRICE	MAT'L UNIT PRICE	TOTAL UNIT PRICE	BID ITEM TOTAL	LABOR UNIT PRICE	MAT'L UNIT PRICE	TOTAL UNIT PRICE	BID ITEM TOTAL	LABOR UNIT PRICE	MAT'L UNIT PRICE	TOTAL UNIT PRICE	BID ITEM TOTAL	LABOR UNIT PRICE	MAT'L UNIT PRICE	TOTAL UNIT PRICE	BID ITEM TOTAL	LABOR UNIT PRICE	MAT'L UNIT PRICE	TOTAL UNIT PRICE	BID ITEM TOTAL				
1010	608	WALK USING PERVIOUS PAVERS, TIER 2 COLOR (LIGHT VEHICULAR TRAFFIC RATING)	1378	SF	3.50	9.50	13.00	17,914.00	4.51	10.25	14.76	20,339.28	3.14	11.18	14.32	19,732.96	6.00	10.00	16.00	22,048.00	7.00	11.00	18.00	24,804.00				
1011	SPECIAL	PERVIOUS PAVERS DELIVERY FEE	1	EACH	850.00	0.00	850.00	850.00	759.00	0.00	759.00	759.00	810.00	0.00	810.00	810.00	800.00	25.00	825.00	825.00	750.00	0.00	750.00	750.00				
1012	SPECIAL	ALUMINUM PAVER EDGING - 3' X 3' X 8'	56	EA	15.00	30.00	45.00	2,520.00	6.60	27.75	34.35	1,923.60	21.00	30.00	51.00	2,856.00	41.00	26.00	67.00	3,752.00	10.00	27.00	37.00	2,072.00				
1013	SPECIAL	EDGE CLAMPING KITS (5 CLAMPING PLATES PER 8' EDGE LENGTH)	8	KIT	65.00	85.00	150.00	1,200.00	7.92	88.13	96.05	768.40	133.00	96.00	229.00	1,832.00	14.00	82.00	96.00	768.00	32.00	88.00	120.00	960.00				
1014	SPECIAL	3/8" X 10" SPIRAL STEEL SPIKES	448	EA	0.65	0.35	1.00	448.00	0.44	0.33	0.77	344.96	0.36	0.36	0.72	322.56	0.10	0.30	0.40	179.20	0.30	0.30	0.60	268.80				
1015	SPECIAL	TOPSOIL FURNISED AND PLACED	8	CY	50.00	25.00	75.00	600.00	27.76	41.25	69.01	552.08	100.00	16.00	116.00	928.00	34.00	22.00	56.00	448.00	30.00	20.00	50.00	400.00				
1016	SPECIAL	SEEDING AND MULCHING	65	SY	4.00	1.00	5.00	325.00	2.96	1.86	4.82	313.30	6.15	0.54	6.69	434.85	1.55	0.30	1.85	120.25	5.00	2.00	7.00	455.00				
1018	SPECIAL	COMMERCIAL FERTILIZER	0.1	TON	0.00	900.00	900.00	90.00	416.46	330.00	746.46	74.65	1,600.00	1,000.00	2,600.00	260.00	100.00	400.00	500.00	50.00	200.00	800.00	1,000.00	100.00				
1019	SPECIAL	WATER	0.4	MGAL	6.00	14.00	20.00	8.00	137.02	13.75	150.77	60.31	640.00	250.00	890.00	356.00	50.00	50.00	100.00	40.00	20.00	80.00	100.00	40.00				
1020	SPECIAL	FILTER FABRIC	250	SY	1.00	0.50	1.50	375.00	1.21	0.46	1.67	417.50	1.69	0.50	2.19	547.50	0.20	0.80	1.00	250.00	0.50	0.50	1.00	250.00				
1021	SPECIAL	GEOGRID - BIAXIAL OR TRIAXIAL	250	SY	1.15	1.10	2.25	562.50	2.97	1.15	4.12	1,030.00	1.11	1.05	2.16	540.00	1.00	2.25	3.25	812.50	0.80	1.20	2.00	500.00				
1202	611	4" SHALLOW PIPE UNDERDRAIN (UNDER PAVER WALKWAY)	280	FT	3.50	2.50	6.00	1,680.00	2.02	0.44	2.46	688.80	5.00	1.50	6.50	1,820.00	1.00	0.50	1.50	420.00	4.00	1.00	5.00	1,400.00				
ALTERNATE BID #1 TOTAL =								33,847.50	ALTERNATE BID #1 TOTAL =				33,952.47	ALTERNATE BID #1 TOTAL =				38,704.87	ALTERNATE BID #1 TOTAL =				38,142.95	ALTERNATE BID #1 TOTAL =				39,374.80
ALTERNATE BID #2 (CONCRETE EDGE)																												
2012	609	ODOT CURB, TYPE 6, AS PER PLAN (0" HEIGHT)	200	LF	13.00	5.00	18.00	3,600.00	2.87	3.10	5.97	1,194.00	12.50	7.50	20.00	4,000.00	19.00	10.00	29.00	5,800.00	18.00	2.00	20.00	4,000.00				
ALTERNATE BID #2 TOTAL =								3,600.00	ALTERNATE BID #2 TOTAL =				1,194.00	ALTERNATE BID #2 TOTAL =				4,000.00	ALTERNATE BID #2 TOTAL =				5,800.00	ALTERNATE BID #2 TOTAL =				4,000.00